

ENQUIRY



HOOGHLY DOCK & PORT ENGINEERS LTD.
(A Government of India Undertaking)
SHIP BUILDERS – SHIP REPAIRERS – ENGINEERS



Registered Office:

1 R.N. Mukerjee Road,
Kolkata – 700 001

Nazirgunge Works:

P.O. Danesh Sk.Lane, Howrah – 711 109
Phone : 2688 7474/76/78
Fax : + 91-033- 2688 6406
Website : www.hooghlydock.gov.in
E-mail : hdpelnw@satyam.net.in

Enquiry No.: CAP/PROJ/NW/105/09-10/E-105/CIVIL.
To

Dated : 24/04/2009.
Due Date : 09/05/2009.

**SUBJECT: CLEANING, LEVELING AND PREPARATION OF
FLOOR OF FOUNDRY SECTION – ‘B’ AT NW.**

Sealed Tenders are invited only from the reputed and experienced contractors for the following job. Party should have authentic papers for taking up such type of job.

Sealed Tenders are invited in two parts, **Part – I:-** giving completion time, terms of payment, equipment required etc. for completion of the job.

Part – II:- Price Bid only on the basis of unit / lump sum as mentioned in the enquiry.

Your quotation should reach us strictly on or before **09/05/2009** in a closed sealed cover mentioning our enquiry no. and due date.

Scope of work:

Excavation / leveling of foundry ‘B’ section as per attached sheet.

HDPEL’s Scope of supply:

Clear site, water and electricity free of charges.

Contractors’ Scope of supply:

Crane, earth mover, earth cutting machine/equipment, vehicle/truck, tools and tackles, gas and gas cutting equipment, sand, cement or any other equipment or materials required for the completion of the job will be the party’s Scope of Supply. Crane/earth cutting equipment must be tyre mounted to prevent damage of metallic road. Necessary tools & tackles, consumable and all other things required to complete the job as per P.O.

.....2.....

NOTE:**=2=**

- 1) This tender may be downloaded from our website www.hooghlydock.gov.in. In that case party must write on the top of the envelope 'From Website'.
- 2) Offer should strictly conform as indicated in the Scope of Work.
- 3) Quotation to be submitted in SEALED COVER with Enquiry No. & Last Date of submission clearly marked on the cover.
- 4) Any Quotation delivered to us after the last date of submission will not be considered.
- 5) Quotation may be rejected if there is any over writing IN THE offer without any signature.
- 6) All the statutory rules have to be complied with as per law of the land.
- 7) Management reserves the right to reject any or all quotations without assigning any reason thereof.
- 8) Job should be done as per direction of the HD(P&M) or his authorized representative.
- 9) Liquidated Damage and Risk Purchase Clauses are applicable as per HDPEL-NW rule.
- 10) Party may send their representative to HDPEL-NW for assessing the job before submitting their final offer. In this regard, party should contact HD(P&M)-NW or his authorized representative from Monday to Friday between 10a.m. to 3p.m. by **08/05/2009**.
- 11) Special care should be taken to prevent any damage of material. Emphasis to be given where ever advised.

SCOPE OF WORK:

SL. NO.	DESCRIPTION	QTY.	RATE	VALUE	REMARKS
01.	Cleaning and removal of garbage of any state and kind, lying at Section-'B'.	To be quoted in lump sum.			
02.	Lifting, shifting and storage/placement of all loose metallic and non-metallic materials scattered within the floor of section - B.	To be quoted in lump sum.			
03.	Dislodging, lifting from grouting and proper placement of machineries having within the floor of section - B.	To be quoted in lump sum.			
04.	Lowering of Crane of fetling shop, demolition of the fetling shop, removal and proper placement of the demolished materials including dismantling or cutting down of arms/brackets etc. from entire section – B.	To be quoted in lump sum.			

05.	Fixing of valley gutter from old dismantled materials after demolition of fetling shop including fixation of down pipe.	10 mtrs. Approx.			
06.	After proper cleaning and removal of all materials/obstruction, floor level to be prepared by cutting or filling of earth as would be required. Level to be maintained as per that of section – C as closed as possible, after rolling with 05 ton Roller. Unit price for rolling to be quoted.	1900 sq.mtrs. (Rate to be quoted in unit-wise.)			
07.	Any concrete construction or grouted steel structure or any thing else coming out of excavation, to be uprooted and shifted or cut down to a safe level below prepared GL.	To be quoted in lump sum.			
08.	To make even surface with the prepared GL, top of drain brick wall within the said area to cut down and mending of the same with sand and cement mortar and proper setting of the cover over it.	To be quoted in lump sum.			

In addition of above

- 1) Materials including excess earth (if any) to be shifted/placed any where within the NW premises as will be directed.
- 2) If excess soil is required for filling/leveling of the floor to be brought from a distance of 250 mtrs. Approx. within NW premises.
- 3) Sketch of the working area is attached herewith.

for HOOGHLY DOCK & PORT ENGINEERS LTD.

S.P. SHOME
(P.O. PROJECT)
(Nazirgunge Works)