



# ENQUIRY

## HOOGHLY DOCK & PORT ENGINEERS LTD.

( A Government of India Undertaking )

SHIP BUILDERS – SHIP REPAIRERS – ENGINEERS



IRQS

AN ISO 9001 UNIT

Registered Office : 1 R.N. Mukerjee Road, Kolkata – 700 001

Nazirgunge Works : P.O. Danesh Sk.Lane, Howrah – 711 109

Phone : 2688 7474/76/78

Fax : + 91-033-2688 6406

e-mail : [hdpelw@satyam.net.in](mailto:hdpelw@satyam.net.in)

Website : [www.hooghlydock.com](http://www.hooghlydock.com)

:  
:Enq. no. HP/PROJ/NW  
98/06-07/E-98  
: Date: 12.05.2008

:  
:Due Date:19.05.08  
:  
:

To  
M/s

Sealed tenders are invited in two parts for Repair / Renovation of damaged shed & roof of workers' canteen of NW as per detailed scope of work (attached Annexure 'I') at Nazirgunge Works:

### **Scope of Work :**

As per Annexure 'I'

Offers are to be submitted in two parts as follows:-

### **Part – I :**

To contain Technical Scope of the work, completion time, applicable taxes, terms of payment, acceptance of L.D. & R.P.Clause etc.

### **Part – II : Only Price ( with break up)**

Both Part I & II under separate cover duly marked and sealed has to be submitted under one cover superscribing the tender enquiry number and due date of submission. Tenders are to be submitted in the Tender Box within due date of submission. Tenders received late shall not be entertained.

for Hooghly Dock & Port Engineers Ltd.

Encl: Annexure 'I'

P.O. (Projects) – NW

Note: Our previous enquiry no. HP/PROJ/SW&NW dt. 22.04.2008 is treated as cancelled.

**SCOPE OF WORK IN DETAIL**

Sr. No.	Description	Rate	Total Cost
1	Removal of existing old damaged sheets, supply and installation of new G.C.I sheets (0.558 mm thk, JINDAL/SAIL Make) with supply of 'J' hook, bolt, nut, washer, etc. complete. 10' – 0" length ..... 44 nos. 8' – 0" length ..... 82 nos.		
2	Dismantling of entire one no. damaged valley gutter (approx. 64' length) at worker canteen, construction and installation of new gutter with supply of Plain G.I. Sheet (0.914 mm thk x 4' x 8') and required fasteners,\. Mimimum 8" lapping to be provided in each joint and 2 coats bituminous paint on entire gutter to be applied.		
3	Necessary repair / replacement of 'J' hook, nut, bolt, limpet washer, etc. as required to prevent leakage of water at dining hall of worker/staff canteen with supply of required materials.		
4	Application of 2 coats coal tar on entire C.G.I sheeted roof surface (outer surface only) worker / staff canteen dining hall with supply of coal tar and other tools & tackles.		
5	Chip out old tar felt, loose master, loose lime concrete etc. from roof surface of entire workers' canteen kitchen, supply and laying 3" thk (average) concrete with cement, sand and stone chip (1:2:3) over 6mm dia reinforcement @ 10" c/c both ways. Surface to be finished with a floating coat of cement slurry.		
6	Removal of damaged portions of ply boards, supply & fixing of new ply board ( 6mm thk, century/Green ply/Ultratake Make) at existing false ceiling after cutting into .....160.00 sq.ft. required sizes		
7	Removal of damaged wooden batons, wooden planks etc. supply & installation of new Sal wood matching with the existing size and shape..... 6.0 cft.		
8	Strengthening of entire false ceiling by providing additional supports from roof truss, frame work etc. as found suitable.		
9	Reinstallation of the eclectic wiring, Tube light shed, fan etc. which are dismantled for repairing of false ceiling.		
10	Supplying & laying single layer plastifelt on C.G.I sheet .....140.00 sq.ft.		